

Observations Log:

Date	Time	Status	Cycle Portion	note:
5-31	10:20	OK	23 °C	start
5-31	11:00	OK	23 °C	
5-31	16:30	OK	- 36 °C / hr	Ramping
6-1	8:30	OK	60 °C	
6-1	16:30	OK	60 °C	
6-2	8:30	OK	+ 84 °C / hr	Ramping
6-2	16:30	OK	+ 84 °C / hr	Ramping
6-5	8:00	OK	60 °C	
6-5	16:30	OK	60 °C	
6-6	8:15	OK	+ 84 °C / hr	Ramping
6-6	16:30	OK	60 °C	
6-7	8:00	OK	23 °C	
6-7	14:30	OK	23 °C	end

Results

The snap on drain closure was tested as received. The cap was not removed prior to or during the test. The test chamber was observed twice daily for seven days during different portions of the cycle as noted. The water did not drip or run from the cap during inspection and there was not evidence of seepage. There was not apparent leaking during the seven day test.

Please contact us if there are any questions.

Sincerely,

LEHIGH TESTING LABORATORIES, INC.



Harvey D. Clements,
Chief Chemist

HDC/cmk
Attachment